

Bid No. 07-10-31

Date: 07/26/2010

Time 2:00 Central Time



LINE Item #	Description	Qty	UOM	5-T Utilities		Doughie Construction		Redrock Construction		Absolute Industries	
				Unit Price	Extended	Unit Price	Extended	Unit Price	Extended	Unit Price	Extended
1	Furnish all materials, labor, equipment and install mobilization including safety issues, & Traffic control signage, and erosion control devices. General cleanup and restoration of site to original including seeding/sod replacement. COMPLETE IN PLACE	1.00	LS	\$ 10,000.00	\$ 10,000.00	\$ 28,500.00	\$ 28,500.00	\$ 6,601.47	\$ 6,601.47	\$ 7,500.00	\$ 7,500.00
2	Furnish all materials, labor, equipment for clearing and grubbing, to include clearing all permanent U.E., hauling debris & complete removal of stumps within 5' both sides of CL trench. COMPLETE IN PLACE.	2.00	AC	\$ 3,500.00	\$ 7,000.00	\$ 8,500.00	\$ 17,000.00		\$ 22,003.83	\$ 5,000.00	\$ 10,000.00
3	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 0'-6' depths. COMPLETE IN PLACE	5.00	LF	\$ 13.00	\$ 65.00	\$ 17.00	\$ 85.00		\$ 6,676.01	\$ 14.83	\$ 74.15
4	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 0'-6' depths with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	5.00	LF	\$ 26.00	\$ 130.00	\$ 21.00	\$ 105.00		\$ 6,676.01	\$ 19.83	\$ 99.15
5	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 6'-8' depths. COMPLETE IN PLACE	778.00	LF	\$ 20.73	\$ 16,127.94	\$ 19.00	\$ 14,782.00		\$ 11,068.47	\$ 18.83	\$ 14,649.74
6	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 6'-8' depths with rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	100.00	LF	\$ 32.00	\$ 3,200.00	\$ 23.00	\$ 2,300.00		\$ 7,215.84	\$ 22.83	\$ 2,283.00

7	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 8'-10' depths. COMPLETE IN PLACE	700.00	LF	\$ 17.00	\$ 11,900.00	\$ 21.00	\$ 14,700.00	\$ 10,625.25	\$ 22.83	\$ 15,981.00
8	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 8'-10' depths with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	122.00	LF	\$ 34.00	\$ 4,148.00	\$ 25.00	\$ 3,050.00	\$ 7,340.85	\$ 26.83	\$ 3,273.26
9	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 10'-12' depths. COMPLETE IN PLACE	600.00	LF	\$ 19.00	\$ 11,400.00	\$ 27.00	\$ 16,200.00	\$ 10,057.01	\$ 24.83	\$ 14,898.00
10	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 10'-12' depths with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	116.00	LF	\$ 38.00	\$ 4,408.00	\$ 31.00	\$ 3,596.00	\$ 7,306.75	\$ 29.83	\$ 3,460.28
11	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 12'-14' depths. COMPLETE IN PLACE	200.00	LF	\$ 21.00	\$ 4,200.00	\$ 31.00	\$ 6,200.00	\$ 7,784.07		\$ 5,366.00
12	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 12'-14' depths with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	210.00	LF	\$ 41.00	\$ 8,610.00	\$ 35.00	\$ 7,350.00	\$ 7,840.89	\$ 39.83	\$ 8,364.30
13	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 12'-14' depths. COMPLETE IN PLACE	50.00	LF	\$ 24.00	\$ 1,200.00	\$ 38.00	\$ 1,900.00	\$ 6,931.72	\$ 32.83	\$ 1,641.50
14	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 14'-16' depths with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	30.00	LF	\$ 48.00	\$ 1,440.00	\$ 42.00	\$ 1,260.00	\$ 6,818.07	\$ 49.83	\$ 1,494.90
15	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 16'-18' depths. COMPLETE IN PLACE	300.00	LF	\$ 27.00	\$ 8,100.00	\$ 42.00	\$ 12,600.00	\$ 8,352.31	\$ 36.83	\$ 11,049.00

16	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 16'-18' depths with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	200.00	LF	\$ 54.00	\$ 10,800.00	\$ 46.00	\$ 9,200.00	\$ 7,784.07	\$ 54.83	\$ 10,966.00
17	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 18'-20' depths. COMPLETE IN PLACE	20.00	LF	\$ 31.00	\$ 620.00	\$ 55.00	\$ 1,100.00	\$ 6,761.25	\$ 38.83	\$ 776.60
18	Furnish all materials, labor, equipment and install 8" PVC SDR 26, 18'-20' depth with rock excavation & haul rock to COH landfill and/or property owner on site. COMPLETE IN PLACE	50.00	LF	\$ 62.00	\$ 3,100.00	\$ 60.00	\$ 3,000.00	\$ 6,931.72	\$ 56.83	\$ 2,841.50
19	Furnish all materials, labor, equipment and install 6" PVC SDR 26, 0'-6' depths. COMPLETE IN PLACE	608.00	LF		\$ 6,080.00	\$ 16.00	\$ 9,728.00	\$ 8,557.44	\$ 12.69	\$ 7,715.52
20	Furnish all materials, labor, equipment and install 6" PVC SDR 26, 6'-8' depths. COMPLETE IN PLACE	557.00	LF	\$ 12.00	\$ 6,684.00	\$ 18.00	\$ 10,026.00	\$ 8,397.24	\$ 16.69	\$ 9,296.33
21	Furnish all materials, labor, equipment and install 6" PVC SDR 26, 8'-10' depths. COMPLETE IN PLACE	311.50	LF	\$ 39.00	\$ 12,148.50	\$ 21.00	\$ 6,541.50	\$ 7,627.08	\$ 20.69	\$ 6,444.94
22	Furnish all materials, labor, equipment and install 6" PVC SDR 26, 10'-12' depths. COMPLETE IN PLACE	100.00	LF	\$ 17.00	\$ 1,700.00	\$ 23.00	\$ 2,300.00	\$ 6,961.72	\$ 22.69	\$ 2,269.00
23	Furnish all materials, labor, equipment and install 6" PVC SDR 26, 12'-14' depths. COMPLETE IN PLACE	262.00	LF	\$ 18.00	\$ 4,716.00	\$ 28.00	\$ 7,336.00	\$ 7,470.59	\$ 26.69	\$ 6,992.78
24	Furnish all materials, labor, equipment and install 6" PVC SDR 26, 14'-16' depths. COMPLETE IN PLACE	300.00	LF	\$ 21.00	\$ 6,300.00	\$ 35.00	\$ 10,500.00	\$ 7,589.95	\$ 30.69	\$ 9,207.00
25	Furnish all materials, labor, equipment and install Trench Protection. COMPLETE IN PLACE	5750.00	LF	\$ 0.50	\$ 2,875.00	\$ 1.00	\$ 5,750.00	\$ 13,436.77	\$ 2.00	\$ 11,500.00

26	Furnish all materials, labor, equipment and install STD. SSMH (6' Depth) with min. 30" ring & cover per spec. COMPLETE IN PLACE	16.00	EA.	\$ 1,950.00	\$ 31,200.00	\$ 2,265.00	\$ 36,240.00	\$ 38,106.42	\$ 2,467.70	\$ 39,483.20	
27	Furnish all materials, labor, equipment and install extra depth SSMH. COMPLETE IN PLACE	59.50	VF.	\$ 382.35	\$ 22,749.82	\$ 175.00	\$ 10,412.50	\$ 13,069.12	\$ 235.00	\$ 13,982.50	
28	Furnish all materials, labor, equipment and install STD SSCO 45 degree with ring & cover for All Depths. COMPLETE IN PLACE	4.00	EA.	\$ 750.00	\$ 3,000.00	\$ 450.00	\$ 1,800.00	\$ 499.78	\$ 1,999.12	\$ 445.36	\$ 1,781.44
29	Furnish all materials, labor, equipment and install 4" SCH PVC 40 sewer stubs @ 2% to ROW/easement line including wyes & bores capped off at natural ground. COMPLETE IN PLACE	29.00	EA.	\$ 900.00	\$ 26,100.00	\$ 550.00	\$ 15,950.00	\$ 4,323.65	\$ 879.87	\$ 25,516.23	
30	Furnish all materials, labor, equipment and install 4" service connection to house, including all TCEQ regulations for abandonment of existing system. COMPLETE IN PLACE	3.00	EA.	\$ 3,900.00	\$ 11,700.00	\$ 1,500.00	\$ 4,500.00	\$ 1,444.94	\$ 967.37	\$ 2,902.11	
31	Furnish all materials, labor, equipment to repair roadway surface with 95% compacted ASTM D1557 cement stabilized sand and 6" compacted limestone, Type A Grade 2. COMPLETE IN PLACE	1.00	LS	\$ 5,000.00	\$ 5,000.00	\$ 16,815.00	\$ 16,815.00	\$ 5,189.71	\$ 5,189.71	\$ 27,500.00	\$ 27,500.00
32	Furnish all materials, labor, equipment and install 8" plug for 8" sewer line. COMPLETE IN PLACE	1.00	EA.	\$ 700.00	\$ 700.00	\$ 375.00	\$ 375.00	\$ 988.72	\$ 988.72	\$ 265.41	\$ 265.41
33	Furnish all materials, labor, equipment and install 8" Top Soil, strip & replacement. COMPLETE IN PLACE	500.00	CV	\$ 4,000.00	\$ 4,000.00	\$ 22.70	\$ 11,350.00	\$ 11.25	\$ 5,625.00	\$ 50.00	\$ 25,000.00
34	Furnish all materials, labor, equipment and bore & encase 10"X3/8" steel casing with plastic spacers & 6" SS SDR 26 SS pipe. Casing to be grouted. All ground conditions. COMPLETE IN PLACE	125.00	LF	\$ 46.00	\$ 5,750.00	\$ 90.00	\$ 11,250.00	\$ 8,807.36	\$ 128.51	\$ 16,063.75	

35 Furnish all materials, labor, equipment and repair concrete and rock driveways to original or better condition. COMPLETE IN PLACE	1.00	LS	\$ 14,400.00	\$ 14,400.00	\$ 9,230.00	\$ 9,230.00	\$ 1,777.94	\$ 1,777.94	\$ 13,717.00	\$ 13,717.00
TOTAL Responders submitted total			\$ 271,552.26	\$ 271,552.26	\$ 313,032.00	\$ 313,032.00	\$ 296,147.34	\$ 296,147.34	\$ 334,355.69	\$ 334,355.69

* 5-T Utilities mathematical error in line # 19 also line # 33 words prevail

* Red Rock excessive mathematical errors Lines 2,3,4,5,6,7,8, 9,10, 11,12,13, 14,15, 16,17,18,19,20,21,22,23,24,25,26,27,29,30,34 words will prevail

* Absolute Industries mathematical error in line # 11 word will prevail

*** NOTICE:** Bid award is contingent upon vendor meeting bid requirements and formal authorization by City officials

BS
 Billie Smith (Purchasing Manager)